

- BARRIER WITH METAL OFFSET BLOCKS IS TO BE REMOVED AND RESET.
- 2. THE CONTRACTOR HAS THE OPTION TO USE SHORTER BOLTS WITH A MINIMUM OF 1/2" PROTRUSION BEYOND NUT.
- 3. WOOD BLOCKS FOR THRIE BEAM PANELS SHALL BE 8×6×22½ INCHES AND NOTCHED AS SHOWN IN THE TOP VIEW. TWO BOLTS ARE REQUIRED FOR ATTACHMENT TO THE POSTS.
- 4. THE 6x6x14 INCH WOOD OFFSET BLOCKS ARE TO BE USED FOR REPAIR WORK ONLY.
- 5. WHEN DIRECTED BY THE ENGINEER OR WHEN SPECIFIED IN THE CONTRACT DOCUMENTS COMPOSITE OFFSET BLOCK AS APPROVED BY THE ADMINISTRATION CAN BE USED IN LIEU OF THE WOOD BLOCKS. FOR THE APPROVED SUBSTITUTES LIST SEE SHEET 1 OF 1 APPROVED SUBSTITUTES FOR WOOD OFFSET BLOCKS.

